

BEST VALUE TASK ORDER PROPOSAL
Date: September 12, 2003
Project Number: DAHA06-03-Q-0029
Project Title: Sidewalks and Pads
Project Description: Install Sidewalks and Concrete Pads at the CT AVCRAD, Groton, CT
Performance Period: 30 Calendar Days
Assessable Liquidated Damages: \$75 Per Day
Offer is due not later than 2:00 PM on: SEPTEMBER 25, 2003 -BID BONDS NOT REQUIRED
You may fax your offer to: (860) 524-4874 or e-mail to: diana.marini@ct.ngb.army.mil
Site Visit: There is no pre-bid site visit scheduled

CONTRACTOR'S OFFER
Offer is:
Acknowledged Amendments
For (Company Name)
Contract Number
By: Typed Name
Signature
Date:

STATEMENT OF WORK**September 12, 2003****DAHA06-03-Q-0029****Install Sidewalks and Pads at the CT AVCRAD**

1. Provide all labor, material, equipment and expertise to install sidewalks and pads at the CT AVCRAD, 139 Tower Ave., Groton, CT 06340. All areas will be excavated and prepped for concrete installation upon removal of the existing areas if the subbase is unsuitable for concrete installation, a proper gravel base will be installed and compacted. All concrete will be 3500 PSI and will have a broom finish to match the existing sidewalks. All disturbed areas will be cleaned, graded and returned to existing conditions upon completion. The sidewalks and pads required are listed below:

Sidewalk – 43'x5'x5", Reinforced walk, 1 each

Sidewalk – 69'x10'x5", Reinforced walk, 1 each

Pad – 14'x7.5'x5", Pad for propane tank with reinforcing

Helicopter Pad – 18'x20'x5"

2. Deliver 120 yards of Pine/Hemlock blend mulch to the CT AVCRAD, 139 Tower Ave., Groton, CT 06340.

3. Work will be completed within 21 days of notice to proceed.

CLIN 001 Install Sidewalks and Pads

\$

Provide all labor, material, equipment and expertise to install sidewalks and pads at the CT AVCRAD, 139 Tower Ave., Groton, CT 06340.

CLIN 002 Deliver Mulch

\$

Deliver 120 yards of Pine/Hemlock blend mulch to the CT AVCRAD, 139 Tower Ave., Groton, CT 06340.