

BEST VALUE TASK ORDER PROPOSAL
Date: JULY 29, 2004
Project Number: W91ZRS-04-Q-0018
Project Title: Land Clearing Project, East Haven Rifle Range
Project Description: Land Clearing Project, East Haven Rifle Range (EHRR), East Haven, CT
Performance Period: 90 Calendar Days
Assessable Liquidated Damages: \$225 Per Day
Offer is due not later than 2:00 PM on: August 20, 2004 –Payment and Performance Bonds ARE required - BID BONDS ARE NOT REQUIRED
You may fax your offer to: (860) 524-4874 or e-mail to: diana.marini@ct.ngb.army.mil
Site Visit: 8:30 AM, AUGUST 6, 2004; EHRR, 591 North High Street, E. Haven, CT 06512
CONTRACTOR'S OFFER
Offer is:
Acknowledged Amendments
For (Company Name)
Contract Number
By: Typed Name
Signature
Date:

BASE BID ITEM

\$ _____

PRIORITY 1: Area X - PROVIDE ALL LABOR, MATERIALS, EXPERTISE, EQUIPMENT, TRANSPORTATION, AND FACILITIES REQUIRED to Clear an area 100' x 1,100', identified as Area X, in accordance with the attached scope of work. This area starts at the east side of the Farm River as it passes the existing firing line of the M203 range and extends north. All brush and trees under 6" in diameter to be "cleared", chipped and blown into the surrounding tree line. Chipped/shredded material will not be piled, it will be spread into the surrounding area and in no case with the depth be more than 6". Trees larger then 6" in diameter will be cut into 8' to 10' lengths and stacked at a location to be specified by Range Control Personnel. These remain the property of the Agency.

ADDITIVE BID ITEM 1

\$ _____

Priority 2: Area Y - PROVIDE ALL LABOR, MATERIALS, EXPERTISE, EQUIPMENT, TRANSPORTATION, AND FACILITIES REQUIRED to clear an area 100' x 1,100', identified as Area Y, in accordance with the attached scope of work. This area is immediately east of, and adjacent to and contiguous with Area X. All brush and trees under 6" in diameter to be "cleared", chipped and blown into the surrounding tree line. Chipped/shredded material will not be piled, it will be spread into the surrounding area and in no case with the depth be more than 6". Trees larger then 6" in diameter will be cut into 8' to 10' lengths and stacked at a location to be specified by Range Control Personnel. These remain the property of the Agency.

SCOPE OF WORK (M-203 RANGE)

The purpose of this request is to select a contractor who will provide the land-clearing services required to further develop the M-203 practice firing range at East Haven Range, 591 North High St, East Haven, CT. See Map at Enclosure A and B.

Site Location: The area in question starts at the east side of the Farm River, where it passes in front of the firing line of the M-203 range, and extends north 1,100 feet. It is 200 feet wide. The area is approximately 5.0 acres. The exact area will be flagged by Agency personnel prior to any pre-bid meeting. See the map at Enclosure C

Following definitions apply:

Clear: To cut and remove all trees and vegetation down to the ground level without disturbing existing sod or grass areas. This definition applies to non-wetlands areas only. See Environmental Requirements below for areas designated as wetland areas by the Agency.

Agency Supplied Materials Required: None

PRIORITY 1: Area X: Base Bid. Clear an area 100' x 1,100'. This area starts at the east side of the Farm River as it passes the existing firing line of the M203 range and extends north.

PRIORITY 2: Area Y: Supplemental Bid 1 Clear an area 100' x 1,100'. This area is immediately east of, and adjacent to and contiguous with Area X.

Specifications for Both Priority 1 and 2:

1. All brush and trees under 6" in diameter to be "cleared", chipped and blown into the surrounding tree line. Chipped/shredded material will not be piled, it will be spread into the surrounding area and in no case with the depth be more than 6".
2. Trees larger than 6" in diameter will be cut into 8' to 10' lengths and stacked at a location to be specified by Range Control Personnel. These remain the property of the Agency.

General Requirements:

1. Pre-Bid meeting: Interested contractors will meet with the Training Site Manager or his representative and contracting personnel from USPFO CT on a date to be determined.
2. Pre-Construction Meeting: The successful bidder will meet with the Training Site Manager or his representative prior to the start of mobilization.
3. All work must be complete no later than 90 days from the Notice to Proceed.
4. All bidders must be experienced in land clearing work similar in design, material as these tasks.

Environmental Requirements

1. Any area flagged by the Agency as wetland will not be clear-cut. Vegetation in these areas can be lowered to 4' high by hand. Trees greater than 8" in diameter will be left untouched. There is to be no disturbance of any wetland area. There will be no vehicle movement or machinery use within wetland areas. Wood chips will be disposed of only in "upland" areas.
2. There will be no soil disturbance within the flood plain or wetland associated with this project.
3. Contractor must abide by local town land clearing regulations. If none exist then State DEP Erosion and Sediment Control Guidelines of 2002 apply.

Enclosures:

- A – Site Location
- B – Site Map
- C- Project Map