

SOLICITATION W91ZRS-04-R-0014
ROAD CLEARING – I & K - SRMR
AMENDMENT 001
September 11, 2004

The following clarifications are provided:

1. Q. Is the silt fence a standard silt fence or is the detail on drawing number C2 to be used? The detail includes wire mesh with the filter fabric.

A. There will be no wire mesh on the filter fabric fence.

2. Q. Will the National Guard mark the areas to be cut?

A. The National Guard will mark the limits of clearing prior to the start of work. Limits of clearing will correspond to the limits shown on the contract plans.

3. Q. Does the silt fence get installed before the land is cleared?

A. If silt fence installation is required, it will be done after clearing is completed.

4. Q. Can any wood be left on site?

A. All trees, brush and other vegetation will be cleared from the areas shown on the contract drawings. All stumps will be cleared flush with the ground. All cleared material up to a diameter of 12" will be chipped on site. Any logs larger than 12" will be loaded and stockpiled at the "airfield" (located 3 miles from the project site).

5. Q. Can the wood chips be left on site?

A. Wood chips will be removed from Stones Ranch Military Reservation by the contractor.