

**W91ZRS-04-R-0018**  
**TUBE RANGE MODIFICATIONS – EHRR**  
**AMENDMENT 001**  
**SEPTEMBER 10, 2004**

1. Q. Please specify what kind of material we are to block existing tubes with, and how much of the tube you wish to block?

A. The tubes should be blocked with concrete block/brick, should only extend into the tube 1 course (1' max), it does not extend down the tube and therefore will not impact the trajectory of any rounds. The purpose of the blocks is to retain the fill material that will be placed at the firing position. See SK-1.

2. Q. Is there supposed to be one #8 rebar across the top, in front and no other rebar? Please clarify.

A. The purpose of the rebar is to define the lower limit of the muzzle control area, it is not a structural element, nor it is it part of the blocking. During our trajectory analysis, this was used as the lower limit that a muzzle would be located.

3. Q. Will contractors be required to spread 4" of topsoil throughout range area prior to seeding? The existing soil appeared to be very sandy and not suitable for planting vegetation.

A. The contractors shall include in their bids, spreading of 4" topsoil prior to seeding.